

Fire Mode Test

Fire Mode Testing is completed as part of the Annual Fire Detection System test, as required by AS1851.

The Fire Mode Test checks the connection between the Fire Indicator Panel and Mechanical Ventilation System and confirms whether it is operating as intended. This test is now required due to the increasingly sophisticated and integrated building systems being installed for building protection.

As part of a buildings conveyancing, a Fire Engineer's Report is produced. The technician uses this report to confirm whether the system is operating

